

# Revive Roof Restoration WA

## Tiled Roof Maintenance Process

<b>1</b>	<b>INSPECT/REPAIR/REPLACE</b> Inspection of entire roof for damage to tiles, valley irons, gutter & downpipe blockages flashings and all roof penetrations and repair to original standard. Repair/replace any job specific works eg. Batons, solar, roof penetrations Damaged tiles and valley irons will be repaired/replaced as per quotation.	
<b>2</b>	<b>HIGH PRESSURE WATER CLEAN (when quoted)</b> Tiles are pressure cleaned at 3000+PSI with straight water using reciprocating waterjet nozzle known as a turbo tip. Entire roof rinsed off before gutters and downpipes flushed clean. Grounds cleanup with all walls, gutters, fascias, paving and sundries all rinsed clean	
<b>3</b>	<b>RE-BED AS REQUIRED AND RE-POINT ALL CAPS</b> Remove and re-bed any caps as required using a cement base. Re-point all ridge/hip cap sides and collars (top) with a flexible adhesive pointing fastening the cap to the roof tile and making watertight.	
<b>4</b>	<b>FINAL CLEAN OF ROOF</b> All debris, dust, sand and matter is removed from the roof surface. All gutters are checked to ensure no debris remains. Inspect to ensure ready for coatings.	
<b>5</b>	<b>COMPLETE SITE CLEAN UP</b> All masking and debris is removed from site. All tools, equipment and damaged tiles removed from site.	
<b>6</b>	<b>FINAL INSPECTION AND REPORT</b> Return to site within 7-14 days for an "on the roof inspection" Check to ensure correct curing and coverage.	